

Submitted to Submitted
Dynegy Midwest Generation, AECOM
LLC 1001 Hig
1500 Eastport Plaza Drive Suite 300
Collinsville, IL 62234 St. Louis

Submitted by AECOM 1001 Highlands Plaza Drive West Suite 300 St. Louis, MO 63110

October 2016

CCR Rule Report: Initial Safety Factor Assessment

For

East Ash Pond

At Havana Power Station

1 Introduction

This Coal Combustion Residual (CCR) Rule Report documents that the East Ash Pond at the Dynegy Midwest Generation, LLC Havana Power Station meets the safety factor assessment requirements specified in 40 Code of Federal Regulations (CFR) §257.73(e). The East Ash Pond is located near Havana, Illinois in Mason County, approximately 0.2 miles east of the Havana Power Station. The East Ash Pond serves as the wet impoundment basin for CCR material produced by the Havana Power Station.

The East Ash Pond is an existing CCR surface impoundment as defined by 40 CFR §257.53. The CCR Rule requires that the initial safety factor assessment for an existing CCR surface impoundment be completed by October 17, 2016.

The owner or operator of the CCR unit must obtain a certification from a qualified professional engineer stating that the initial safety factor assessment meets the requirements of 40 CFR § 257.73(e). The owner or operator must prepare a safety factor assessment every five years.

2 Initial Safety Factor Assessment

40 CFR §257.73(e)(1)

The owner or operator must conduct initial and periodic safety factor assessments for each CCR unit and document whether the calculated factors of safety for each CCR unit achieve the minimum safety factors specified in (e)(1)(i) through (iv) of this section for the critical cross section of the embankment. The critical cross section is the cross section anticipated to be the most susceptible of all cross sections to structural failure based on appropriate engineering considerations, including loading conditions. The safety factor assessments must be supported by appropriate engineering calculations.

- (i) The calculated static factor of safety under the long-term, maximum storage pool loading condition must equal or exceed 1.50.
- (ii) The calculated static factor of safety under the maximum surcharge pool loading condition must equal or exceed 1.40.
- (iii) The calculated seismic factor of safety must equal or exceed 1.00.
- (iv) For dikes constructed of soils that have susceptibility to liquefaction, the calculated liquefaction factor of safety must equal or exceed 1.20.

A geotechnical investigation program and stability analyses were performed to evaluate the design, performance, and condition of the earthen dikes of the East Ash Pond. The exploration consisted of hollow-stem auger borings, cone penetrating testing, and laboratory program including index testing. Data collected from the geotechnical investigation, available design drawings, construction records, inspection reports, previous engineering investigations, and other pertinent historic documents were utilized to perform the safety factor assessment and geotechnical analyses.

In general, the subsurface conditions at the East Ash Pond consist of medium dense to very dense embankment fill (sand and gravel) overlying very loose to medium dense alluvial sand, which in turn overlies bedrock. Phreatic water is within the foundation of the East Ash Pond.

Three (3) representative cross sections were analyzed using limit equilibrium slope stability analysis software to evaluate stability of the perimeter dike system and foundations. The cross sections were located to represent critical surface geometry, subsurface stratigraphy, and phreatic conditions across the site. Each cross section was evaluated for each of the loading conditions stipulated in §257.73(e)(1).

The Soils Susceptible to Liquefaction loading condition, §257.73(e)(1)(iv), was not evaluated because a liquefaction susceptibly evaluation did not find soils susceptible to liquefaction within the East Ash Pond dikes. As a result, this loading condition is not applicable to the East Ash Pond at the Havana Power Station.

Results of the Initial Safety Factor Assessments, for the critical cross-section for each loading condition (i.e., the lowest calculated factor of safety out of the cross sections analyzed for each loading condition), are listed in **Table 1**.

§257.73(e)(1) Minimum Factor of Calculated Factor of **Loading Conditions** Subsection Safety Safety Maximum Storage Pool Loading 1.50 2.10 (i) Maximum Surcharge Pool Loading (ii) 1.40 2.10 Seismic 1.00 1.51 (iii) 1.20 Soils Susceptible to Liquefaction Not Applicable (iv)

Table 1 – Summary of Initial Safety Factor Assessments

Based on this evaluation, the East Ash Pond meets the requirements in §257.73(e)(1).

3 Certification Statement

CCR Unit: Dynegy Midwest Generation, LLC; Havana Power Station; East Ash Pond

10/3/16

I, Victor A. Modeer, PE, being a Registered Professional Engineer in good standing in the State of Illinois, do hereby certify, to the best of my knowledge, information, and belief that the information contained in this CCR Rule Report, and the underlying data in the operating record, has been prepared in accordance with the accepted practice of engineering. I certify, for the above-referenced CCR Unit, that the initial safety factor assessment dated October 2, 2016 meets the requirements of 40 CFR §257.73(e).

Printed Name

Date

About AFCOM

AECOM (NYSE: ACM) is a global provider of professional technical and management support services to a broad range of markets, including transportation, facilities, environmental, energy, water and government. With nearly 100,000 employees around the world, AECOM is a leader in all of the key markets that it serves. AECOM provides a blend of global reach, local knowledge, innovation, and collaborative technical excellence in delivering solutions that enhance and sustain the world's built, natural, and social environments. A Fortune 500 company, AECOM serves clients in more than 100 countries and has annual revenue in excess of \$19 billion.

More information on AECOM and its services can be found at www.aecom.com.