CCR Fugitive Dust Control Plan

for Havana Power Station

Prepared for:



Havana Power Station 15260 N. State Route 78 Havana, IL 62644

Prepared by:



October 2015

Table of Contents

1 Introduction		1-1
1.1 1.2	Facility Information Certification	
2 CCF	R Fugitive Dust Control Measures and Appropriateness	2-1
2.1 2.2 2.3	Management of CCR in the CCR Units Handling of CCR Transportation of CCR	
4 Rec 5 Pro	cedures for Periodic Assessment of the Plan ordkeeping, Notification, Internet Site cedures to Log Citizen Complaints ulatory Cross Reference	4-1 5-1
7 Am	ulatory Cross Reference	6-1 7-1

List of Tables

Table 2-1.	Control Measures for CCR Management in CCR Units	2-3
	Control Measures for Handling CCR	
	Control Measures for Transportation of CCR	
	CCR Fugitive Dust Control Plan Regulatory Cross Reference	
Table 7-1.	CCR Fugitive Dust Control Plan Amendments	7-1

Introduction 1

This Coal Combustion Residuals (CCR) fugitive dust control plan has been prepared for the Havana Power Station, located in Mason County, Illinois. This plan addresses the 40 CFR 257.80 air operating criteria of the United States Environmental Protection Agency's CCR rule, which requires the owner or operator of a CCR unit to adopt measures that will effectively minimize CCR from becoming airborne at the facility and to prepare and operate in accordance with a CCR fugitive dust control plan.

1.1 **Facility Information**

- Facility Name: Havana Power Station

062.064098

- Facility Address: 15260 N. State Route 78
- Owner/Operator: Dynegy Midwest Generation, LLC

1.2 Certification

The owner or operator must obtain a certification from a qualified professional engineer that the initial CCR fugitive dust control plan, or any subsequent amendment of it, meets the requirements of 40 CFR 257.80.

I certify under penalty of law that, to the best of my knowledge, this plan meets the requirements of 40 CFR 257.80. This certification is based on my review of the document and conditions at the site and on my inquiry of the person or persons who managed the preparation of this document.

Wendy. M. Pennington 1. Printed Name of Qualified Professional Engineer Wedy M. P. J. 10/7/15

Signature of Qualified Professional Engineer and Date



expires 11/30/15 Illinois **Registration Number and State**

2 CCR Fugitive Dust Control Measures and Appropriateness

CCR fugitive dust has the potential to become airborne at the facility during periods of CCR management in the CCR units, CCR handling and CCR transport. Areas at the facility that have the potential for airborne CCR fugitive dust are CCR surface impoundments, CCR handling equipment and CCR transport in trucks or railcars. This section identifies and describes the control measures selected and adopted by the facility to minimize CCR from becoming airborne at the facility and explains how the selected measures are applicable and appropriate for site conditions. The control measures may be adjusted or modified based on observed effectiveness of minimizing CCR from becoming airborne and weather conditions.

2.1 Management of CCR in the CCR Units

The facility manages CCR in surface impoundments located at the facility. Table 2-1 below identifies CCR fugitive dust control measures that have been selected for use by the facility during CCR management in the CCR units, including placement of CCR into the CCR unit, and explains how the selected measures are applicable and appropriate for site conditions. The facility will use the identified measures during CCR management in the CCR units to minimize CCR from becoming airborne at the facility.

CCR Activity	CCR Fugitive Dust Control Measure	Applicability and Appropriateness of Control Measure
	Wet management of CCR bottom ash and CCR fly ash in CCR surface impoundments.	Wet management of CCR minimizes the potential for CCR fugitive dust generation.
	Water areas of exposed CCR in CCR units, as necessary.	Water will be applied to areas of exposed CCR to maintain moisture content to minimize the potential for CCR fugitive dust generation in excessively dry or windy conditions.
Management of CCR in the facility's CCR units	Water dry CCR material from periodic cleanout / maintenance of CCR handling or CCR dust control systems as it is added into the CCR surface impoundments, as necessary.	Wetting CCR reduces the potential for CCR fugitive dust generation during addition to surface impoundments.
	Naturally occurring grass vegetation in areas of exposed CCR in CCR surface impoundments.	Vegetation provides a wind screen and/or cover and reduces wind entrainment of CCR.
	Apply chemical dust suppressant on areas of exposed CCR in CCR units, as necessary.	Mixing an appropriate chemical dust suppressant with water and applying to areas of exposed CCR will minimize the potential for CCR fugitive dust generation in excessively dry or windy conditions.

Table 2-1. Control Measures for CCR Management in CCR Units

2.2 Handling of CCR

CCR is regularly removed from the boiler system and conveyed to the CCR handling system, which includes silos and truck/railcar loading areas. CCR fly ash is pneumatically conveyed in an enclosed system from the boiler system to storage silos. CCR fly ash is loaded dry into bulk transporters utilizing a vented spout. CCR fly ash may also be conditioned prior to being loaded into trucks for transport. Both CCR bottom ash and CCR fly ash are wet sluiced into a CCR surface impoundment. Bottom ash is periodically removed from the CCR surface impoundments and remains sufficiently wet during and after handling activities, including dewatering, associated with transfer of the CCR. CCR spray dryer absorber (SDA) waste ash is transported to the CCR surface impoundment in CCR transport trucks. Occasionally, CCR from the maintenance of dust handling equipment or dust control equipment is loaded into a vacuum truck and transported to the CCR units. Table 2-2 below identifies CCR fugitive dust control measures that have been selected for use by the facility during handling of CCR and explains how the selected measures are applicable and appropriate for site conditions. The facility will use the identified measures when handling CCR to minimize CCR from becoming airborne at the facility.

CCR Activity	CCR Fugitive Dust Control Measure	Applicability and Appropriateness of Control Measure
	Wet sluice CCR bottom ash and CCR fly ash to CCR surface impoundments.	Wet sluicing CCR minimizes the potential for CCR fugitive dust generation.
	CCR bottom ash removed from CCR surface impoundments and loaded into trucks for transport remains conditioned during handling.	Wetting CCR allows CCR to bind together and thus minimizes the potential for CCR fugitive dust generation when CCR is handled.
	Pneumatically convey dry CCR fly ash to storage silos in an enclosed system.	Conveying CCR fly ash in an enclosed system minimizes the potential for CCR fugitive dust generation.
Handling of CCR at	Load CCR transport trucks from the CCR SDA waste ash silo in a partially enclosed area.	Partial enclosure of the CCR transport truck loading area reduces the potential for wind to cause CCR fugitive dust to become airborne.
the facility	Load CCR transport trucks from the CCR fly ash silos using a vented loadout spout.	Use of a vented loadout spout reduces the drop height from the end of the chute into the truck and minimizes the potential for CCR fugitive dust to become airborne.
	Perform housekeeping, as necessary, in the fly ash and SDA waste ash loading area.	Good housekeeping measures, such as sweeping or wetting the loading area, minimizes the potential for CCR fugitive dust generation during handling activities.
	Operate fly ash and SDA waste ash handling system in accordance with good operating practices.	Operation in accordance with good operating practices minimizes the potential for CCR fugitive dust generation.
	Maintain and repair as necessary dust controls on the fly ash and SDA waste ash handling system.	Maintenance and repairs are performed as needed to maintain dust controls in good operating condition to minimize the potential for CCR fugitive dust generation.

Table 2-2. Control Measures for Handling CCR

CCR is transported via truck at the facility using unpaved facility roads. Table 2-3 below identifies CCR fugitive dust control measures that have been selected for use by the facility during transport of CCR on facility owned CCR haul roads. The facility will use the identified measures when transporting CCR to minimize CCR from becoming airborne at the facility.

CCR Activity	CCR Fugitive Dust Control Measure	Applicability and Appropriateness of Control Measure
	Cover or enclose trucks/railcars used to transport CCR fly ash.	Covering or enclosing trucks/railcars transporting CCR minimizes the potential for CCR fugitive dust generation from the CCR transport trucks/railcars.
	Limit the speed of vehicles to no more than 15 mph on facility roads used to transport CCR.	Limiting the speed of vehicles traveling on facility roads minimizes the potential for CCR fugitive dust generation from the CCR transport trucks.
Transportation of CCR at the facility	Cover or enclose trucks used to transport CCR other than fly ash, as necessary.	Covering or enclosing trucks transporting CCR on facility roads minimizes the potential for CCR fugitive dust generation from the CCR transport trucks.
	Sweep or rinse off the outside of the trucks transporting CCR, as necessary.	Removing CCR present on the outside of the truck minimizes the potential for movement of the truck or wind to cause CCR fugitive dust to become airborne.
	Watering facility roads used to transport CCR materials, as needed.	Watering CCR haul roads minimizes the potential for CCR fugitive dust generation in excessively dry or windy conditions.

Table 2-3. Control Measures for Transportation of CCR

3

The facility conducts inspections associated with CCR fugitive dust control. The facility also uses the procedures identified in section 5 of this plan to log citizen complaints involving CCR fugitive dust events at the facility. These inspections and the investigations of citizen complaints will be used to periodically assess the effectiveness of the CCR fugitive dust control plan.

The facility routinely performs inspections to verify the effectiveness of the CCR fugitive dust control measures used at the facility. Inspections are conducted during daylight working hours and include observing for the presence of CCR fugitive dust emissions from vehicles transporting CCR on facility roads, CCR handling and CCR management, including CCR placement in CCR units. Inspection records include information such as the name of the person conducting the inspection, the date and time of the inspection, the results of the inspection, and any corrective action taken.

When a CCR fugitive dust event is observed or a citizen complaint involving a CCR fugitive dust event at the facility is received, current CCR management practices will be reviewed to see that the selected control measures are being properly implemented. If the control measures are not being properly implemented, relevant operating personnel will be notified and, as warranted, re-trained in the proper implementation of CCR fugitive dust control measures. If appropriate, use of revised and/or additional control measures will be evaluated. As warranted, revised and/or additional control measures found to be applicable and appropriate to control CCR fugitive dust emissions will be incorporated into an amended CCR fugitive dust control plan.

The plan also will be reassessed in the event of material changes in site conditions potentially resulting in CCR fugitive dust becoming airborne at the facility.

4 Recordkeeping, Notification, Internet Site

The written CCR fugitive dust control plan, any amendment of the written plan, and the annual CCR fugitive dust control report required by 40 CFR 257.80(c) will be placed in the facility's written operating record and posted to the Internet site in accordance with 40 CFR 257.105(g) and 257.107(g). Notification of the availability of the CCR fugitive dust control plan, any amendment of the plan, and the annual CCR fugitive dust control report will be provided to the State Director in accordance with 40 CFR 257.106(g).

5 Procedures to Log Citizen Complaints

In the event the owner or operator of the facility receives a citizen complaint involving a CCR fugitive dust event at the facility, relevant information about the complaint will be logged. Information that will be recorded includes, as applicable:

- Date/Time the complaint is received
- Date/Time and duration of the CCR fugitive dust event
- Description of the nature of the CCR fugitive dust event
- Name of the citizen entering the complaint
- Address & phone number of citizen entering the complaint
- Name of the personnel who took the complaint

All citizen complaints involving CCR fugitive dust events at the facility will be investigated promptly. As deemed appropriate or necessary, corrective measures will be taken and a follow-up response will be provided to the complainant.

40 CFR 257 Citation	Regulatory Requirement	CCR Fugitive Dust Control Plan Section
.80(b)(1)	Identify and describe CCR fugitive dust control measures the owner or operator will use to minimize CCR from becoming airborne at the facility. Explanation of how the CCR fugitive dust control measures selected are applicable and appropriate for site conditions	2
.80(b)(3)	Procedures to log citizen complaints involving CCR fugitive dust events at the facility	5
.80(b)(4)	Periodic assessment of effectiveness of CCR Fugitive Dust Control Plan	3
.80(b)(5)	Date of initial CCR Fugitive Dust Control Plan	7
.80(b)(6)	Amendment of CCR Fugitive Dust Control Plan	7
.80(b)(7)	Certification of CCR Fugitive Dust Control Plan	1.2

Table 6-1. CCR Fugitive Dust Control Plan Regulatory Cross Reference

7 Amendments

The written CCR fugitive dust control plan may be amended at any time provided the revised plan is placed in the facility's operating record as required by 40 CFR 257.105(g(1)). The written CCR fugitive dust control plan must be amended whenever there is a change in conditions that would substantially affect the written plan in effect.

Amendment Number and Date	Pages or Section	Description of Amendment	Professional Engineer Certifying Plan
Version 0 October 2015		Initial Plan	Wendy M. Pennington

Table 7-1. CCR Fugitive Dust Control Plan Amendments